



Project Profile

Board Machine Rebuild

South Africa

Pre-appropriation engineering, including process diagrams, general layouts and cost estimates was carried out for the rebuild of an existing board machine.

A speed increase was realized increasing production tonnage from 150 to 270 TPD. The machine rebuild included 7 Kobayashi formers and a new Stock Preparation area (top liner, under liner, filler (3), back under liner, back liner).

Services: process design, basic engineering, cost estimate